


R16 XFMR & SVC RWMD DENTRO DE LOMAS PRELIMINARY SKETCH



300000544374

NOTES

CUSTOMER IS RESPONSIBLE FOR:

- *TRENCH, EXCAVATION AND BACKFILL
- *CONDUIT (INCLUDING REDUCERS & ADAPTERS AT HANDHOLES)
- *SUBSTRUCTURES
- *CONCRETE/SIDEWALK BREAK & REPAIR
- *RETAINING WALLS

MAINTAIN A MINIMUM OF 5' WHEN PARALLELING WET UTILITIES AND 6" WHEN CROSSING

MAINTAIN 5' CLEARANCE BETWEEN TRANSFORMER PADS AND ALL WINDOW OPENINGS

MAINTAIN 5' CLEARANCE BETWEEN VEHICULAR TRAFFIC AND PADMOUNTED EQUIPMENT

IT IS THE CUSTOMER'S RESPONSIBILITY TO PROVIDE TRENCH AND CONDUIT TO THE ENERGIZED SOURCE. EMPTY CONDUIT STUBS ARE INSTALLED FOR THE FUTURE USE OF THE UTILITY. IF THE STUB IS UNUSABLE, THE CUSTOMER MAY CLEAN OR REPAIR THE STUB, OTHERWISE, INSTALL NEW TRENCH AND CONDUIT TO THE SOURCE.

24 HOUR LINE TRUCK ACCESS TO SDG&E DISTRIBUTION AND SERVICE FACILITIES REQUIRED.

